

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 27 W


Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 5-6-7-8

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/20/64 with Klawiter and Lane

WITNESSES TO CORNER..... 6" Elm (S5 NBT), N 68° E, 36½ Dcs.



7" Basswood (in clump) (S8 NBT), S 05° E, 32½ Dcs.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportioned measurement from Section Corners, 1 mile to North, East and West and 1/4 Corner 1/2 mile South. No Original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 10/14/1964
REGISTERED LAND SURVEYOR