

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 27 W


Menominee COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections 4-9

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/29/64 with R. Hinds

WITNESSES TO CORNER..... 12" Cedar (1/4S NBT) S 74° E, 20 1/2 Lks.



8" Cedar (1/4S NBT), N 76° W, 22 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced at two Wood Posts which were in proper distance and bearing to down Tamarack with inverted scribe marks on overgrowth and visible and badly rotted Spruce stump.

SURVEYOR'S SEAL

SIGNED *Frank J. Bray*
FRANK J. BRAY
REGISTERED LAND SURVEYOR DATE 10/14/1964