

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 27 W


Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections ~~3-4-9-10~~

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/1/64

WITNESSES TO CORNER..... 5" Ash (S3 NBT), N 24° E, 39 Lks.



8" Ash (S9 NBT), S 46° W, 29 Lks.

6" Ash (S4 NBT), N 63° W, 49 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established from Double Proportioned measurement. Wood Post found within a few links distance.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 10/14/1964
REGISTERED LAND SURVEYOR