

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	31 T. 37 N. S., R. 27 E.	A-12
2. PROPERTY CONTROLLING IN SECTION	31 T. 37 N. S., R. 27 E.	10
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MENOMINEE  
CO

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 12, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<p>A-12 West 1/4 corner Sec. 31 Wood post Cedar 10 - S80°W - 04 Tam. 10 - N55°E - 22</p>	<p>10 S 1/16 corner on West Section line Not previously marked.</p>
--	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-12 Set from stump of cedar O.B.T. recorded as cedar 10 - S80°W - 04 - tam. roots in place for N.E. O.B.T. Cedar stump shows burned out upper & lower face and a "T" in the overgrowth on upper face. The E-W position of this corner is also verified by a very old tam. stub about 300' south with a definite blase on both north and south sides and about 2" of overgrowth on the blases. Believed marked as a sight tree on the original gov't survey.

10 Set M.P.O.L. between the west 1/4 corner and the S.W. section corner (twp. cor.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>A-12 1" pipe, 4" aluminum cap 7" cedar N84°E - 13.8' 7" cedar N66°W - 9.1' 8" cedar N11°W - 21.2'</p>	<p>10 1" pipe, 4" aluminum cap Cedar post 6" sugar maple N51°W - 17.4' 18" W. pine N1°W - 70.25' 4" sugar maple S36°W - 2.75'</p>
--	---

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_