

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>37</u> N. S., R. <u>27</u> E. W.	A-11, C-11
2. PROPERTY CONTROLL- ING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12/10, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- A-11 - SW Sec. Cor. of Section 30; wood post - Tam. 6" - N70°E - 63 lks; Tam. 8" - S80°E - 57 lks.; Tam. 8" - N50°W - 19 lks.; Tam. 10" - S75°W - 32 lks.
 - C-11 - S.E. Cor. of Section 30; wood post - Lynn 10" - N70°E - 14 lks.; W. Pine 24" - S58°W - 8 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- A-11 - Set in center line of E-W road at 79.2 ft. (G.L.O. record Mea.) West of small stream. This falls in line with old Cedar posts North and South.
 - C-11 - Set by double Prop. Mea. to the G.L.O. record using Section Corners 1 mile North & 1 mile East and 1/4 Cors. 1/2 mile West & 1/2 mile South. Several W.P. stumps in the area but could not identify any as being an O.B.T.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-11 - 1" pipe, 4" aluminum cap; 16" Willow (Twin) S75°W 104.00'; 4" W. Birch - N62°E - 37.4'; 2" pipe for gate - S88°E 31.0'; 7" Cedar S64°E 66.0'.
 - C-11 - 1" pipe, 4" aluminum cap; 10" (Twin) Sugar Maple N61°W 25.8'; 9" Sugar Maple North 31.4'; 11" Lynn N85°E 17.9'; 13" Sugar Maple S19°W 5.3'.

SIGNED BY David B. Babbitt DATE 12-16-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____