

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>37</u> N. S., R. <u>27</u> E. W.	E-9 & C-9
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 19, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-9 - Southeast section corner of Section 20; wood post, Tam. 12" - N20W - 35 lks.; Tam. 6" - S26E - 62 lks.
- C-9 - Southwest corner of Section 20; wood post, Cedar 10" - N30E - 22 lks.; Tam. 12' - S30W - 18 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-9 - Set in centerline of E-W blacktop road with mea. prop. to the G.L.O. record between the South 1/4 corner of Section 20 and the S 1/4 corner of Section 21.
- C-9 - Set in centerline of E-W blacktop road and in line with old fence lines North and South. G.L.O. swamp calls "South 1.50" and "West 4.35" fit very well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-9 - Menominee County survey monument set flush with blacktop surface; 5" Tamarack N33°W 42.7'; 7" Tamarack N4°W - 40.2'; 5" Tamarack N62°E - 78.1'; Power Pole S13°W - 71.2'.
- C-9 - Menominee County survey marker; 9" Cedar N10°E - 44.1'; 9" Tamarack N32°E - 48.2'; 4" Tamarack N57°E - 95.7'; Gate Post - S31°E - 35.0'.

SIGNED BY David B. Babbitt DATE 12-16-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____