

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>37N</u> N. S., R. <u>27W</u> E. W.	B-11, C-10
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12/10, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-11 - $\frac{1}{2}$ corner of Section 30; wood post - Cedar 8" - N34W - 27 lks.; Tam. 10" - S58E - 40 lks.
- C-10 - $\frac{1}{2}$ corner Section 30; wood post - Sugar 10 - N50°E - 41 lks.; W. Pine 18 - S28°W - 34 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-11 - Set from stps. of both O.B.T.s Cedar 8" N24°W - 27 lks. is now a stub 4' tall with marks of overgrowth for both upper and lower faces but too badly burned for scribe marks. Tam. 10" S 58°E - 40 lks. is a stump cut low and is very rotten but still shows signs of scarring and overgrowth. Also found remains of a cedar stp. 4 ft. north of this corner with a flat axe blaze facing the corner but with no other marks and not of record. Bearings and distances to both O.B.T.s are good.
- C-10 - Set M.P.O.L. betw. the N.E. & S.E. section corners of Section 30.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-11 - 1" pipe, 4" aluminum cap; 4" Cedar N54°W 20.3'; 5" Cedar N40°E 12.2'; 6" Cedar S50°E 19.0'; 7" Cedar S51°W 17.8'.
- C-10 - 1" pipe, 4" aluminum cap; 9" Cedar N30°W 20.6'; 6" Hemlock N34°E 10.9'; 4" Balsam Fir S30°E 12.4'; 10" Hemlock S30°W 36.8'.

SIGNED BY David B. Babbitt DATE 12-16-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____