

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION _____ 29 _____ T. _____ 37 _____	N. _____ E. _____ S., R. _____ W. _____	14, 15, 16
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12/10, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 14 - S 1/16 corner - East section line of Section 29; not previously established.
- 15 - W 1/16 corner on the South section line of Section 29.; not previously established.
- 16 - East 1/16 corner on the South section line of Section 29; not previously established.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- 14 - Set M.P.O.L. between the East 1/4 corner and the S.E. section corner of Section 29.
- 15 - Set M.P.O.L. between the S1/4 corner and the S.W. section corner of Section 29.
- 16 - Set M.P.O.L. between the S1/4 corner and the S.E. section corner of Section 29.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 14 - 1" pipe, 4" aluminum cap; 10" Sugar Maple N89°E 20.7'; 9" Sugar Maple S65° 12.0'; 6" (Twin) Sugar Maple S36°W 36.8'; 12" (Twin) Sugar Maple S85°W 38.4'.
- 15 - 1" pipe, 4" aluminum cap; 5" Cedar S26°E 9.1'; 6" Cedar S52°W 6.7'; 4" Cedar N13°W 5.5'; 5" Cedar N56°E 6.8'.
- 16 - 1" pipe, 4" aluminum cap; 22" W. Spruce N5°W 40.3'; 9" Cedar N19°E 59.0'; 4" B. Ash S55°E 19.0'; 8" Cedar S16°E 35.4'.

SIGNED BY David B. Babbitt DATE 12-16-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_