

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>37N</u> N. S., R. <u>27W</u> E. W.		<u>C-5, A-4.</u>
2. PROPERTY CONTROLLING IN SECTION _____ , T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

MENOMINEE
C.O.

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 11, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-5. SE sec. cor. of Section 7. Wood post. Cedar 12 - N38W, 19 Lks.
W. Ash 14 - S83W, 39 Lks.

A-4. West $\frac{1}{4}$ cor. of Section 7. Wood post. W. Pine 20 - S40^oW, 12 Lks.
Y. Pine 18 - N42^oW, 40 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-5. Set from remains of 12" cedar OBT, N38W, 19 Lks. Down and quite badly burned but parts of both upper and lower fact still visible. Remains of a very rotten stump fall in exact position of the SW O.B.T. Calls for "overflowed swale" north, east & west are all reasonable.

A-4. Set M.P.O.L. between the NW and SW sec. cors. of Section 7. Pine stumps in the area but could not identify O.B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5. DNR Monument.	A-4. DNR Monument.
6" Bl. Ash S72 ^o W, 37.4'	8" R. Pine - S6 ^o E, 94.3'
4" Bl. Ash N18 ^o W, 44.8'	2" W. Pine - N79 ^o E, 49.6'
6" Bl. Ash N34 ^o E, 41.3'	2" R. Pine - S56 ^o W, 23.3'
7" Bl. Ash S41 ^o E, 52.7'	1" R. Pine - (not marked) N58 ^o W W-21.8'

Corner falls in a small wet marsh about 30' from its n.westerly edge.

SIGNED BY

David B. Babbitt

DATE

1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE