

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>37N</u> N. S., R. <u>27W</u> E. W.	B-5.
2. PROPERTY CONTROLLING IN SECTION <u>7</u>	, T. <u>37N</u> N. S., R. <u>27W</u> E. W.	16, 15
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MEMORIAL

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 11, 19 84, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 16) East 1/16 cor. on the south sec. line of Section 7. Not prev. est.
- 15) West 1/16 cor. on the south sec. line of Section 7. Not prev. est.
- B-5) South 1/4 cor. of Section 7. Wood post. B. Ash 5 N35°E - 10 Lks.  
B. Ash 10 - S39°W - 52 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 16) Set M.P.O.L. between the S $\frac{1}{4}$  cor. and the SE sec. corn. of Section 7.
- 15) Set by single proportion betw. the S $\frac{1}{4}$  cor. and the SW sec. cor. of Section 7.
- B-5) Set by single proportion between the Se and SW sec. cors. of Section 7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                        |                           |                        |
|------------------------|---------------------------|------------------------|
| 16) DNR Monument.      | 15) DNR Monument          | B-5) DNR Monument      |
| 4" spruce S37°E, 21.4' | 4" ironwood N75°W, 15.6'  | 9" cedar N81°E, 7.15'  |
| 5" balsam S35°W, 29.1' | 8" ironwood S59°W, 16.85' | 4" cedar S12°E, 20.3'  |
| 3" spruce N9°W, 23.3'  | 6" basswood S25°E, 10.1'  | 7" cedar S45°W, 10.15' |
| 4" spruce N33°E, 8.3'  | 5" maple N76°E, 26.8'     | 6" spruce N41°W, 4.9'  |

SIGNED BY

*David B. Babbitt*

DATE

1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE