

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>19</u>	T. <u>37N</u> N. S., R. <u>27W</u> E. W.	C-8, B-7
2. PROPERTY CONTROLLING IN SECTION <u>19</u>	, T. <u>37N</u> N. S., R. <u>27W</u> E. W.	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

MLNOMINER
C

I, David Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 4, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 7) North 1/16 on east section line of Section 19. Not prev. est.

C-8) East 1/4 corner of Section 19. Wood post. Beech 6 - N50E - 28 Lks.
 Fir 6 - S40W - 34 Lks.

B-7) North 1/4 corner. Wood post.
 Hem. 9" N19°E - 27 Lks.
 Hem. 10" - S44°W - 31 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 7) Set MPOL between the east 1/4 corner and the NE section corner of Section 19.

C-8) Set at very old fence corner. SE section corner of Section 19 is S00°-01'-02"E 2614.45' from this point and the NE section corner is N00°-35'-04"W 2629.11'.

B-7) Set DNR mon. in E of N-S road and in line with very old fences east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

7) DNR Monument	C-8 DNR Monument	B-7) 1" pipe 4" alum. cap
13" Sugar Maple N60°W 21.1'	4" Blasam Fir N42°W 56.4'	8" Sugar Maple N37°W 32.7'
12" Beech S13°W 27.4'	9" Sugar Maple N77°W 34.0'	9" Sugar Maple N16°E 44.1'
4" Sugar Maple N50°E 46.0'	5" Tamarack S58°E 98.0'	10" twin Sugar Maple S42°W 69.3'
10" Sugar Maple S82°W 2.25'	10" Red Pine N51°E 134.2'	NW corner of concrete block camp. S41°E 72.9'

SIGNED BY: David B. Babbitt DATE 1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____