

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>17</u> T. <u>37N</u> N. S., R. <u>27W</u> E. W.		<u>15, 16, 14.</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MONUMENTED

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 9, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 15) West 1/16 corner on the south section line of Section 17. Not prev. est.
- 16) East 1/16 corner on the south section line of Section 17. Not prev. est.
- 14) South 1/16 corner on the east section line of Section 17. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 15) Set MPOL between the south 1/4 corner and the SW section corner of Section 17.
- 16) Set MPOL between the south 1/4 corner and the SE section corner of Section 17.
- 14) Set MPOL between the east 1/4 corner and the SE section corner of Section 17.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------|--------------------------|-----------------------------|
| 15) DNR Monument | 16) DNR Monument | 14) DNR Monument |
| 4" cedar N29°E 15.75' | 9" b. cherry S72°E 48.4' | 12" sugar maple N83°E 9.35' |
| 5" cedar S42°E 25.05' | 7" cedar N29°E 71.5' | 14" lynn S28°E 12.8' |
| 9" cedar S62°W 42.3' | 4" cedar N6°E 50.4' | 5" sugar maple S13°W 25.65' |
| 9" cedar N64°W 34.6' | 13" r. maple S39°W 50.1' | 9" sugar maple N30°W 31.7' |

SIGNED BY

David B. Babbitt

DATE

1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

DATE _____