

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u> T. <u>37N</u> N. S., R. <u>27W</u> E. W.		<u>F-5, G-7.</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MEMORIAL

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 4, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-5) N1/4 corner of Section 16. Wood post. Cedar 12 N28E - 14 Lks.
Cedar 14 S62W - 35 Lks.
- G-7) SE section corner of Section 16. Wood post. W. Pine 10 N54W 27 Lks.
Cedar 18 S13E - 9 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-5) Found the points of four old cedar posts in a cluster in line with the center of an old road grade east. Edge of swamp 1.42 chs. East fits very well with GLO record. This position is very near MPOL between iron bars 1/2 mile east and 1/2 mile west. Set DNR mon.
- G-7) Found iron rod with stump remains in place for both OBT's. Too rotted to show any marks of the original survey but species and size are correct, swamp calls 3 chs. E and 2.14 chs. S are reasonable. Mea. to known corners N-S & W compare favorably with other measurements in this twp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---------------------------|--------------------------|
| F-5) 1" pipe 4" alum. cap | G-7) DNR mon |
| 8" cedar S56°E 25.6' | 12" cedar S85°E 62.7' |
| 8" cedar S82°W 39.2' | 5" w.spruce S20°E 30.3' |
| 8" cedar N70°W 43.9' | 5" w.spruce S56°W 73.0' |
| 6" cedar N18°E 46.1' | 5" balsam fir N8°E 18.3' |

SIGNED BY David B. Babbitt DATE 1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____