

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>18</u>	T. <u>37N</u> N. S., R. <u>27W</u> E. W.	<u>C-7, C-6.</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

*MENOMINEE CO*

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 4, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-7) SE section corner of Section 18. Wood post. Beech 12 N78E - 20 Lks.  
 Beech 14 S65W - 30 Lks.  
 C-6) East 1/4 corner of Section 18. Wood post. Beech 8 N80E-26 Lks.  
 Hem. 8 S72W - 19 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-7) Set by extending a line from the south 1/4 corner of Section 18 easterly across a very old fence corner at the E 1/16 corner on the south section line of Section 18, which is said by local land owners to have been set by survey in the mid-nineteen thirties, and double the distance between said two points.  
 C-6) Set MPOL between the NE and SE section corners of Section 18. No sign of OBT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                          |                            |
|--------------------------|----------------------------|
| C-7) DNR Mon.            | C-6) DNR Monument          |
| 9" Maple S33°E 17.7'     | 10" W.Ash N47°W 24.6'      |
| 4" Maple N74°E 8.35'     | 5" Sugar Maple N44°E 3.1'  |
| 5" Ironwood N22°W 32.95' | 6" W.Ash S29°E 29.7'       |
| 13" Beech S74°W 38.7'    | 5" Sugar Maple S76°W 15.4' |

SIGNED BY David B. Babbitt DATE 1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_