

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>37N</u> N. S., R. <u>27W</u> E. W.	<u>E-7, F-7, E-8.</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

*MEMORIAL*

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 27, 19 84, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-7. NW corner of Section 21. Wood post. Hem. 14 N13W - 40 Lks.  
Cedar 12 S39E - 59 Lks.
- F-7. North 1/4 corner of Section 21. Wood post. Fir 8 - N34W - 22 Lks.  
Hem. 12 S47E - 33 Lks.
- E-8. West 1/4 corner of Section 21. Wood post. Cedar 8 N78W - 12 Lks.  
Spruce 5 S50E - 21 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-7. Set by double proportion to the record of the original gov't. survey, using section corners, 1 mile north, 1 mile east, and 1 mile south and the 1/4 corner 1/2 mile west. Could not identify any original bearing trees or line trees at this time.
- F-7. Set MPOL between the NE and NW section corners of Section 21. No sign of OBT's.
- E-8. Set MPOL between the NW and SW section corners of Section 21. No sign of OBT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7. D.N.R. Monument	F-7. 1" pipe-4" alum cap	E-8. D.N.R. Monument
4" Balsam Fir S62°W 32.1'	4" Balsam Fir S55°E 15.0'	4" Cedar S15°W 16.6'
10" Cedar N34°E 40.3'	4" Balsam Fir S38°W 17.15'	4" Cedar N76°W 13.7'
8" Cedar N73°E 17.4'	4" Balsam Fir N15°E 14.15'	5" Cedar N19°W 10.4'
9" Cedar S69°E 28.9'	8" W. Birch N51°W 48.5'	4" Cedar N59°E 14.0'

SIGNED BY David B. Babbitt DATE 1-14-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_