

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>17</u>	T. <u>37N</u> N. S., R. <u>27W</u> E. W.	<u>E-6, D-5, D-7.</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MEMORIAL

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 9, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- E-6. East 1/4 corner of Section 17. Wood post. B. ash N41W - 35 Lks. (No size given.)
B. ash S36E - 33 Lks.
 - D-5. North 1/4 corner of Section 17. Wood post. Maple 12 N30E - 52 Lks.
Y. Birch 12 S54W - 66 Lks.
 - D-7. South 1/4 corner of Section 17. Wood post. Cedar 12 N58E - 24 Lks.
Cedar 12 S40W - 35 Lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- E-6. Set MPOL between the NE and SE section corners of Section 17.
 - D-5. Set MPOL between the NE and NW section corners of Section 17. No sign of OBT's.
 - D-7. Found sq. cedar post in swamp. Cedar stumps in place for both OBT's. No marks left on the SW one but the NE one has a definite hack mark at the bottom of the lower blaze.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | | |
|---------------------------|---------------------------|---------------------------|
| E-6. DNR Monument | D-5. DNR Mon. | D-7. DNR Monument |
| 4" cedar N54°E 34.5' | 4" tamarack N17°W - 95.8' | 5" cedar N83°E 12.4' |
| 5" cedar N84°E 27.8' | 7" balsam N20°W - 29.3' | 6" cedar N32°W 9.6' |
| 8" balsam fir S25°E 40.2' | 8" cedar N31°W - 90.1' | 5" cedar S69°W 21.3' |
| 5" b. ash S3°E 21.6' | 7" maple N69°W - 52.5' | 5" b. spruce S38°E 11.75' |

SIGNED BY David B. Babbitt DATE 1-16-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____