

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>17</u>	T. <u>37N</u> N. <u>27W</u> S., R. _____ E. W.	<u>2, 1, 7.</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

*MONUMENTED*

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 9, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- 2) East 1/16 corner on the north section line of Section 17. Not prev. est.
  - 1) West 1/16 corner on north section line of Section 17. Not prev. est.
  - 7) North 1/16 corner on the east section line of Section 17. Not prev. est.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 2) Set MPOL between the north 1/4 corner and the NE section corner of Section 17.
  - 1) Set MPOL between the north 1/4 corner and the NW section corner of Section 17.
  - 7) Set MPOL between the east 1/4 corner and the NE section corner of Section 17.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |                         |                          |                          |
|-------------------------|--------------------------|--------------------------|
| 2) DNR Mon.             | 1) DNR Monument          | 7) DNR Monument          |
| 13" maple S51°W 5.2'    | 8" oak N10°W 27.15'      | 4" B. ash S7°W 24.5'     |
| 10" maple N48°W 27.4'   | 4" w. ash S65°E 12.25'   | 9" Oak West 15.1'        |
| 9" maple N57°E 11.6'    | 9" oak S22°W 31.5'       | 4" R. Maple N61°E 16.55' |
| 6" ironwood N14°E 24.3' | 9" b. cherry S80°W 8.25' | 8" Oak N39°W 9.0'        |

SIGNED BY

*David B. Babbitt*

DATE

*1-16-85*

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE