

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>17</u>	T. <u>37N</u> N. S., R. <u>27W</u> E. W.	<u>E-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____	, RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

*MENOMINEE COUNTY*

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 23, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

N.E. corner of Section 17. Wood post. Hem. 16 - N54E, 27 Lks.  
Hem. 14 - S30W, 42 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found axle shaft of unknown origin. Fits well with other known corner monuments in the area. Replaced axle shaft w/D.N.R. mon.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument  
5" Balsam fir S47°W 133.4'  
3" Balsam fir N69°W 58.5'  
9" Black cherry N32°E 81.25'  
4" B. spruce S31°E 40.8'

SIGNED BY David B. Babbitt DATE 9-26-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: