

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ T. _____ | N. _____ E. _____ S., R. _____ W. | _____ |
| 2. PROPERTY CONTROLLING IN SECTION <u>18</u> , T. <u>37N</u> | N. <u>27W</u> E. _____ S., R. _____ W. | <u>12; 13; 11.</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ | N. _____ E. _____ S., R. _____ W. | _____ |
| 4. LOT NO. _____ , RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

*MENOMINEE
COUNTY*

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 23, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 12. South 1/16 of Section 18. Not previously established.
- 13. SE 1/16 cor. of Section 18. (Ctr. of SE 1/4). Not previously established.
- 11. SW 1/16 cor. of Section 18. (Ctr. of SW 1/4-Section 18). Not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 12. Set M.P.O.L. between the S 1/4 cor. and the center of Section 18.
- 13. Set at the center of the SE 1/4 of Section 18 by closed traverse.
- 11. Set at the center of the SW 1/4 of Section 18, by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--------------------------|----------------------|------------------------|
| 12. DNR (Buried in road) | 13. DNR Monument | 11. DNR Monument |
| 4" W. Spruce N60°E 40.6' | 5" Cedar S23°E 26.6' | 5" Spruce N14°W 36.2' |
| 8" Beech S48°E 47.95' | 6" Cedar S8°W 18.5' | 11" Spruce N35°E 23.6' |
| 9" W. Birch N50°W 113.1' | 5" Cedar N51°W 16.8' | 5" Spruce S75°E 37.1' |
| 6" B. Cherry S82°W 19.8' | 6" Cedar N24°E 32.6' | 8" Spruce S20°W 34.6' |

SIGNED BY _____

David B. Babbitt

DATE _____

9-26-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)