

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>37N</u> R <u>27W</u>	<u>D06</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>17</u> T <u>37N</u> R <u>27W</u>	<u>06</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		9		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Jeremy J. Pipp, in a field survey on 12/19/2012AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D06) Center One-Quarter Corner of Section 17. Not set in original survey, no evidence of subsequent establishment.

(06) Northeast One-Sixteenth corner of Section 17. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D06) Corner position established at the intersection of the North-South and East-West One-Quarter lines of Section 17.

(06) Corner position established at the intersection of the North and East One-Sixteenth lines of Section 17.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D06) DNR monument  
 8" Maple N47E 29.69' (1/4S,BT)  
 12" Basswood S42E 20.58' (1/4S,BT)  
 12" Maple S40W 11.57' (1/4S,BT)  
 10" Maple N71W 27.78' (1/4S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

(06) DNR monument  
 14" Basswood N75E 13.62' (1/16S,BT)  
 7" Basswood S35E 16.10' (1/16S,BT)  
 9" Maple S50W 36.17' (1/16S,BT)  
 12" Basswood N51W 7.93' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by Jeremy J. Pipp  
 Surveyor's Michigan License No. 50447



Date July 18, 2013

For the Michigan Department of Natural Resources, Forest Resource Division

20158

20156