

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Menominee	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 6 T 37N R 27W	3
	S 6 T 37N R 27W	14
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, Jeremy J. Pipp, in a field survey on 3/19/2012AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(03) North One-Sixteenth corner common to Sections 6 and 1. Not set in original survey, 1961: Kimberly Clark (Neil Sprhake, PS#7876) 5-9-61: Set Galvanized 1" Iron Pipe, 3 feet long with Aluminum cap; Maple 14 N22E 23 1/2 links (15.51') Basswood 8 S20W 60 links (39.60'); 2002: Coleman Engineering (James Moore, PS#28423): Set 5/8" Rebar with Cap, no witnesses taken.

(14) South One-Sixteenth corner common to Sections 5 and 6. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(03) Corner position established by single proportionate measurement between the West One-Quarter corner and the Northwest corner of Section 6. Found PS#7876 Pipe bent laying flat, and existing NE Maple BT (now overgrown 25" Dia., and a mound of dirt pushed against base.). Also Found PS#28423 rebar bent & laying flat. Position in North edge of woods road and 0.5 feet East of existing Gate. Monumented position checks within reason to existing BT.

(14) Corner position established mid-point and on-line between the East One-Quarter corner and the Southeast corner of Section 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(03) DNR monument  
 EX. 25" Sugar N34E 16.29' ( - , - )  
 4" Ironwood S17E 29.43' (1/16S,BT)  
 13" Sugar S56W 35.62' (1/16S,BT)  
 4" Ironwood N32W 45.08' (1/16S,BT)

(14) DNR monument  
 10" Spruce N72E 25.63' (1/16S,BT)  
 10" Spruce S32E 25.55' (1/16S,BT)  
 10" Twin Spruce S35W 15.65' (1/16S,BT)  
 4" Cherry N20W 8.00' (1/16S,BT)

Steel gate posts; North 3.9' & South 15.3' All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by Jeremy J. Pipp  
 Surveyor's Michigan License No. 50447

**JEREMY J. PIPP**  
 Date July 16, 2012  
 PROFESSIONAL SURVEYOR

For the Michigan Department of Natural Resources, Office of Land and Facilities

