

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

| MENOMINEE (County) | Located In: | Corner Code # |
|---------------------------------------|-----------------------------|---------------|
| 1. Public Land Survey | T <u>37</u> N R <u>27</u> W | <u>G-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTERED FOR RECORD
 97 JUL 23 PM 3:35
 PAGE # 503 BK 5
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE, MI 49859
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, William Lenca, in a field survey on Feb. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Y. Birch, 12" - N46°E - 56 lks.; Hemlock, 10" - N85°W - 64 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 5/8 inch diameter iron rod was found in the centerline of a county road running South from this location, and in line with an ancient fence line running East, along with 3 Cedar B.T.'s with cross cut in upper and lower blaze. This position is further supported by an old fence at the 1/16 line a quarter mile South which splits the half mile distance between the W1/4 Corner (G-4) and the SW Corner (G-5) of Section 10, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Accepted existing 5/8" dia. Iron/sct 3-1/4" dia. Alum. cap stamped for corner:

| | | | |
|------------------------------------|-------|------------|----------------------------------|
| 6" dia. Cedar (Ex. B.T.) | S71°E | 28.00 feet | Cross cut in upper & lower blaze |
| 7" dia. Cedar (Ex. B.T.) | S14°E | 48.10 feet | Cross cut in upper & lower blaze |
| 6" dia. Cedar (Ex. B.T.) | S76°W | 42.46 feet | Cross cut in upper & lower blaze |
| 8" dia. Wood Gate Post in concrete | N10°W | 43.61 feet | |
| Metal Survey Sign Post | N40°W | 17.9 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Apr. 01, 1997



REMONUMENTATION

503

DEC 20 1997

COMMISSION