

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. of 1990 On 12/12 1996

For corners in

<u>MENOMINEE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T_{37N} R_{27W}</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on Oct 14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Cedar, 18" - N04°W - 21 lks; Elm, 16" - S43°E - 24 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1964: L.C.R.C. No. 386 (Vol. 2) by Frank Bray, DNR Surveyor, states that a 1-1/4" x 12" Axle Shaft was set at point of old wood post reported to be corner by local resident. B.T.'s - 6" Fence Post - S28°E - 42.5 links; 6" Fence Post - S43°W - 54 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1-1/4" diameter Axle Shaft and the points of the 2 fence post ties as noted in part "A" above. The corner falls in line with the centerline of a county road running North and 5 feet South of the centerline of a county road running East. This corner has been accepted and used as the corner position by surveyors and local residents for over 40 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location over existing Axle Shaft:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N35°E	43.26 feet	0.5' S. of Cor. Fc. Post
10" dia. Tamarack	S13°E	53.97 feet	Scr. NBT
12" dia. Cedar	S33°W	99.92 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S42°W	54.04 feet	0.5' S. of Cor. Fc. Post
Metal Survey Sign Post	South	24.20 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Oct. 31, 1996

Chairman: DEC 20 AM 9:34
 # 383, BK 4
 REGISTER OF DEEDS
 REGISTERED FOR RECORD

