

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of

For corners in

MENOMINEE
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 37N R 27W _____ G-6

T _____ R _____ _____

T _____ R _____ _____

T _____ R _____ _____

2. Property Controlling in Section

S _____ T _____ R _____ _____

S _____ T _____ R _____ _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____ _____

S _____ T _____ R _____ _____

P.A. Of 1990 On 12/16 1996

Alan Davis Chairman

RECEIVED FOR RECORD
 26 DEC 20 AM 9:33
 # 282, BK 4
 MARGARA KONTSON
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, William Lenca, in a field survey on Oct 14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Hemlock, 12" - N39°E - 17 lks; Cedar, 18" - S64°W - 56 lks. All original evidence for this corner has been destroyed by farming activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We computed the single proportional position for this corner and searched the area. The corner position falls in a small meadow with no original evidence apparent and no occupational evidence. The land on both sides of the Section Line running between Sections 15 and 16 has been owned for many years by the same family. We set the corner at the single proportional position and accepted this location as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

8" dia. Tamarack	N33°E	59.32 feet	Scr. NBT
9" dia. Tamarack	S22°E	68.81 feet	Scr. NBT
9" dia. White Spruce	N65°W	122.23 feet	Scr. NBT
Metal Survey Sign Post	North	1.05 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Oct. 31, 1996