

SURVEY

APR 06 1999

SECTION

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/14 1998
McJannet RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>37N</u> R <u>27W</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTERED FOR RECORD
99 JAN 27 PM 1:34
PAGE # 756 8X5
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
(SAME AS CORNER G-01, T36N - R27W)

I, William Lenca, in a field survey on Aug. 17, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by H. Brevoort, Jr. (Township Boundary) - B.T.'s - Sugar, 14" - N60°W - 33 lks.; Birch, 24" - N33°E - 21 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1852: Original Survey by Francis Coleman (Sectional Subdivision) - B.T.'s - Sugar, 12" - S26°E - 28 lks.; Hemlock, 9" - S54°W - 29 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: L.C.R.C. No. 305 by William Lenca, RLS No. 26461, states "Set corner in center of N-S Co. Rd. and in line with ancient stone & wire fence to the west. This position checks well with GLO ties N-S-W." Set 3/4" x 18" Iron Pipe: Fc Post - Scr. B.P. - N60°E - 37.32'; 10" Elm - Scr NBT - S16°E - 110.68'; PP - S38°W - 60.89'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 3/4" x 18" Iron Pipe in the centerline of a North - South County Road and in line with an ancient rock and wire fence to the West per L.C.R.C. No. 305. We also recovered the Elm B.T. and the Power Pole witness described in part "A". The corner falls 12' North of a County Road centerline to the East. This position has been consistently used by local surveyors for at least 17 years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long 3-1/4" dia. Alum cap stamped for corner location:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N48°E	33.55 feet	1' N. of Road Sign
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S36°E	56.15 feet	1' W. of Fence Post
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S39°W	60.09 feet	1' E. of P.P.
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N75°W	25.22 feet	@ Sign Post
Metal Survey Sign Post	N75°W	26.1 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Aug. 25, 1998

756