

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

McDermis DCS

For corners in
MENOMINEE
 (County)

Located in: Corner Code #

1. Public Land Survey T37N R 27W L4
 T R
 T R
 T R

2. Property Controlling in Section
 S T R
 S T R
 S T R

3. Miscellaneous Property in Sec.
 S T R

REGISTERED FOR RECORD
 97 JUL 23 PM 3:35
 PAGE # 505, BR5
 BARBARA MERRISON
 REGISTER OF DEEDS
 MENOMINEE COUNTY, MICHIGAN
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

William Lenca Mar. 07 97
 I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10	●	11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Hemlock, 16" - N16°W - 26 lks.; Sugar, 10" - S55°E - 47 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner was set in line with the centerline of a North - South County Road, and in line with ancient fences running East and West. This corner fits well with other corners in the area, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	East	24.48 feet	
5" dia. Spruce	S80°W	36.77 feet	Scr. NBT
16" dia. Cedar	N25°W	71.30 feet	Scr. NBT
Mctal Survey Sign Post	East	25.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Apr. 01, 1997
 Surveyor's Michigan License No. 26461

REMONUMENTATION

DEC 2 1997
 COMMISSION

505