

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/12 1996

Mc Davis PL's  
Chairman

RECEIVED FOR REPORT  
5 DEC 20 AM 9:33  
# 376, BK 4  
BARBARA MONROE  
REGISTERED PROFESSIONAL SURVEYOR

Register of Deeds Stamp & File Number

For corners in

MENOMINEE  
(County)

Located In:

Corner Code #

1. Public Land Survey

T7N R27W 17  
T R  
T R  
T R

2. Property Controlling in Section

S T R  
S T R  
S T R

3. Miscellaneous Property in Sec.

S T R  
S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Oct. 24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Sugar, 18" - N26°W - 60 lks; Hemlock, 18" - S47°E - 42 lks. All original evidence for this corner has been destroyed by clearing and farming activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We set this corner on line with ancient fences running East - West and South. The fence line running south has been removed for approximately 1000 feet to enlarge the field, however, the corner fence post is still evident. This corner location fits well with measurements to corners 1 mile North and 1 mile West, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

Triple Elm, 30" dia. at base	South	1.47 feet	to 60d in E. face
14" dia. Elm	West	53.79 feet	Scr. NBT
Nothing else nearby	S28°W	24.44 feet	Scr. NBT

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Oct. 31, 1996

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date \_\_\_\_\_