

APR 06 1999

Approved by Menominee County Land Survey Reorganization Peer Group Under Act 345 Of P.A. Of 1990 On 12/14/98
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

1. Public Land Survey

T37N R 27W

I-11

2. Property Controlling in Section

S
S
S
S

T
T
T
T

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD
99 JAN 27 PM 1:34
PAGE # 761 BKS
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on July 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Cedar, 10" - N25°W - 19 lks.; Cedar, 10" - S32°E - 19 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1965: Plat of Survey by Robert Olsen shows this corner as being in the center of County Roads East - West - North, and in line with a fence to the South.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a railroad spike in the centerline of County Roads East - West - North, and in line with an old fence to the South set over a 10" long iron spike 1 foot below the road surface. This position fits well with Robert Olsen's 1965 Survey, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

- 10" dia. Cedar N58°E 64.18 feet Scr. NBT
- 6" dia. Tamarack S52°E 96.29 feet Scr. NBT
- 5" dia. Cedar S38°W 67.52 feet Scr. NBT
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" N43°W 36.07 feet 1' North of Road Sign
- Metal Survey Sign Post South 27.3 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sept. 29, 1998

