

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1996 On 12/30 1997
Mr. Louis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located In:	Corner Code #
T 37N R 26W	A-12
T 37N R 27W	(M-12) ✓
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

REGISTERED FOR RECORD
97 DEC 30 PM 4:06
PAGE # 417 OF 5
BARBARA WOODRIF
REGISTER OF DEEDS
MENOMINEE COUNTY
REGISTER OF DEEDS STAMP & FILE NUMBER

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
(SAME AS CORNER M-12 T37N-R27W)

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Lenca, in a field survey on Dec. 08, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Birch, 6" - N50°W - 15 lks.; Cedar, 4" - S57°W - 26 lks. All original evidence for this corner has been destroyed by C. & N.W. Railroad construction.
- 1990: L.C.R.C. No. 881 by William Lenca states, "Set corner on line with NE & SE Section Corners & in line with an old fence line to the West. This position fits well with the occupied 1/16 line to the South." Set 3/4" x 60" Alum. rod/3-1/4" dia. Alum. cap stamped for corner location. TIES: Nail in Telegraph Pole - S83°E - 98.40'; Nail in Telegraph Pole - S13°E - 151.93'; Inside W'y Rail - S89°E - 73.20'; Cedar, 12" - S40°W - 61.47'; 2" dia. I.P. - S47°E - 19.47'; 2" dia. I.P. - S77°W - 5.27'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 3/4 inch x 60 inch Aluminum rod with a 3-1/4 inch diameter Aluminum cap stamped for corner location (stamped 1990) in a position as indicated in L. C. R. C. No. 881. This corner has been accepted and used for surveys in the area, fits existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 3/4" x 5' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner location:

8" dia. Cedar	N53°E	44.33 feet	Scr. NBT
6" dia. White Pine	S61°E	18.31 feet	Scr. NBT
6" dia. Cedar	S68°W	35.09 feet	Scr. NBT
8" dia. Cedar	N40°W	10.78 feet	Scr. NBT
Carsonite Survey Marker	West	1.0 feet	
Ex. 1-1/2" dia. Iron Pipe	S82°W	5.24 feet	
West Rail C. & N.W. Railroad	East	74.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 15, 1997

