

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 37. NR. 28. W. . .

Menominee

COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 16, 21 . . . . .

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap . . . . .

WITNESSES TO CORNER 20" Red Pine S 42° W 63 links  
Marked "1/4 S NBT"

8" Soft Maple S 80° E 4 1/2 links  
Marked "1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from two Yellow Pine stumps badly burned, in proper position. Squared cedar stake in place.

Corner lies 1/2 ch. North of E & W trail road.

1/4 Corner found by C. Limpert, District Forester.

Corner placed and witnessed December 21, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 1-11-57  
REGISTERED LAND SURVEYOR