

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~317~~ NR. 28 W.

Menominee COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sec.'s 32-33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 12" Red Oak S 82° W 43 links

Marked "1/4 S NBT"

10" W. Pine N 50° E 75 links

Marked "1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner as set by J.C. Lymer, surveyor, in 1927.

Found wood post scribed with roman numerals in place.

1/4 Corner lies 1 ch. south of woods road.

1/4 Corner found by Forestry Division Survey Crew while making a partial re-survey in this township.

Record of this 1/4 Corner found at Wisc.-Mich. Power Company office at Iron Mountain.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 4/16/57