

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 36-37 NR. 28 W . . .

Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 4-5-32-33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

|                     |               |                   |           |
|---------------------|---------------|-------------------|-----------|
| WITNESSES TO CORNER | 12" W. Pine   | N 45° W           | 112 links |
|                     |               | Marked "S 32 NBT" |           |
|                     | 6" Red Oak    | S 63° E           | 74½ links |
|                     |               | Marked "S 4 NBT"  |           |
|                     | 6" Soft Maple | S 36° W           | 76 links  |
|                     | (clump)       | Marked "S 5 NBT"  |           |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Corner as set by J.C. Lymer, surveyor, in 1927.

Found 3/4" iron bar and scribed wood post.

Record of this Corner found at Wisc.-Mich. Power Company office at Iron Mountain.

Corner found by Forestry Division Survey Crew while making a partial re-survey of this township.

Corner lies 1 ch. west of woods road.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 4/16/57  
REGISTERED LAND SURVEYOR