

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37. NR. 28. W.

Menominee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 26, 27, 34 and 35
DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.
WITNESSES TO CORNER 6" Soft Maple S 16 W 26¹/₂ Links, marked S 34 MBT
8" Red Oak N 85 E 70¹/₂ Links, marked S 26 MBT
7" Red Oak S 44 E 78¹/₂ Links, marked S 35 MBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from possible B.T. (W. Pine stump, S 75 W 25 Links). This position fits well with 1/4 corner 1/2 mile North and Section corner 1 mile South.

This area has been badly burned.

Corner lies 50 Links East and 19 Links South of 40.00 chains.

Corner placed and witnessed on 14 July 1958.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 4-17-59
REGISTERED LAND SURVEYOR