

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 28 W


Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 27-28-33-34

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10/29/64 with R. Hinds

WITNESSES TO CORNER..... 12" S. Maple (S33 NBT), S 15° W, 26 Lks.



9" S. Maple (S27 NBT), N 22° E, 29 Lks.

7" Cedar (S 34 NBT), S 39° E, 49 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportioned measurement between Section Corners 1 mile to E., W., N., and S. No Original Evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 12/9/1964
REGISTERED LAND SURVEYOR