

MENOMINEE

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74. MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION _____	28, T. 37 N. _____ E. _____ S. _____ R. 28 W. _____	4, 5, 6
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 15 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 4 N.W. 1/16 corner - Section 28 (center of N.W. 1/4). A 1-1/4" iron rod set by unknown person(s), and not of record is 13.65' S40°W from this corner.
- 5 North 1/16 corner - Section 28; not previously established.
- 6 N.E. 1/16 corner - center of the N.E. 1/4 of Section 28; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 4 Set at the computed center of the N.W. 1/4 of Section 28 by closed traverse.
- 5 Set M.P.O.L. between the computed center of Section and the North 1/4 corner of Section 28.
- 6 Set at the computed center of the N.E. 1/4 of Section 28 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL 1" pipe, 4" aluminum cap.
- 4 7" Oak - N86°E - 43.1'; 6" Maple - S54°E - 27.4'; 7" Oak - S85°W - 13.6';  
1-1/4" Iron Rod - S40°W - 13.65'.
  - 5 7" Cedar - S52°E - 24.5'; 6" Cedar - S13°W - 43.7'; 12" Cedar - N51°W - 42.9';  
10" Cedar - N50°E - 61.9'.
  - 6 5" W. Birch - S38°W - 27.4'; 6" W. Birch - N62°W - 9.0'; 7" W. Birch - N38°E - 23.6';  
7" Spruce - S82°E - 54.85'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 7-13-81  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558