

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... T. 37 N. S., R. 28 E. W. E-9, F-9, G-9
2. PROPERTY CONTROLLING IN SECTION... T. N. S., R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION... T. N. S., R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 30 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

- A. Description of original monument and accessories and/or subsequent restoration:
E-9 N.W. section corner - Section 28. Nothing recorded in J.C. Lymer survey for this section corner, however, he must have had a corner here to set 1/16 corners north and south as shown on his survey map. Co. Road plans - Proj. 771(2) show road P.I. as Sec. Cor.
F-9 North 1/4 corner - Section 28. Shown on Menominee Co. Rd. plans (Proj. 771(2)) as "1/4 corner" no N.B.T.'s given.
G-9 N.E. section corner - Section 28. County Road plans show road P.I. as section corner proj. #771(2).

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
E-9 Set on line with and double the distance between the W. 1/4 corner and the N. 1/16 corner on the west section line of Sec. 28. Said corners set in a survey by J.C. Lymer in 1927 and marked with Wisconsin-Michigan Power Co. monuments. Old square post on north side of road. Measurement east fits record measurement on Co. Rd. plans - Proj. 771(2)
F-9 Set D.N.R. monument in Mon. box - 2' north of centerline of Pvmt. This corner was re-established as shown on Menominee Co. Rd. plans Proj. #771(2). Fits existing occupation well.
G-9 Set in the position established by Frank Bray R.L.S. in a survey in Secs. 27 & 28 done in 1964. Falls in approx. centerline of E-W blacktop rd. Old sq. post on south side of road.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Measurement west fits record measurement on Co. Rd. Plans. Proj. #771(2).
ALL 1" pipe, 4" aluminum cap in monument box.
E-9 7" Cedar - S5°W - 36.7'; 11" Cedar - S45°E - 49.55'; 8" Cedar - N28°E - 38.1'; 6" Cedar - N9°W - 34.5'.
F-9 8" Spruce - S07°E - 43.95'; 8" Maple in clump - S25°W - 45.0'; 5" W. Birch - N15°W - 38.7'; 1-1/4" Pipe - N01°W - 37.6'; 1/2" Pipe - South - 26.6'.
G-9 7" W. Pine - S40°E - 37.3'; 7" W. Pine - N40°E - 68.1'; 7" Cedar - S66°W - 87.4'; 6" Maple - N60°W - 54.0'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt MICHIGAN REGISTERED LAND SURVEYOR DATE 7-13-81 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558