

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--------------------------------------|---|--------------------|
| 1. PUBLIC LAND SURVEY | T. <u>37</u> N. <u>X</u> , R. <u>28</u> E. <u>W</u> . | <u>I-7</u> |
| 2. PROPERTY CONTROLLING IN SECTION | , T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION | , T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____ |
| 4. LOT NO. _____ | RECORDED PLAT _____ | _____ |
| 5. PRIVATE CLAIMS _____ | _____ | _____ |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 26, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

N.W. section corner of Sec. 23
Mich. Dept. of Conservation 7-14-58

Original bearing trees: beech 10" - S63°W - 33 Lks.
Y. pine 24" - S80°E - 24 Lks.

Replaced corner from y. pine stump bearing S80°E - 24 Lks. Found old wood post in place. Position fits top of ridge 1½ chs. south and stream and swamp edge 6½ chs. east.

N.B.T.s 11" red pine - S31°W - 105½ Lks.
14" red pine - N88°W - 113½ Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found sq. scribed cedar post with both Conservation Dept. N.B.T.s and the stump of the y. pine O.B.T. in place as described. Set D.N.R. monument in place of scribed post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. monument

7" red pine - N51°W - 66.7'
Re-marked old N.B.T. 20" red pine - N88°W - 74.9'
Re-marked old N.B.T. 15" red pine - S34°W - 69.3'
16" y. pine stp. w/old face & two hacks - S 7°W - 36.4'
Y. pine stp.- S62°E - 15.8'

SIGNED BY

David B. Babbitt

DATE

19-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: