

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 37 N. XX R. 28 E. W.	I-8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 27, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

West 1/4 corner of Sec. 23

Mich. Conservation Dept. 2-14-63

Re-established midway and on line between two section corners.
Found no evidence of original corner.

N.B.T.s 8" bl. spruce - N47°W - 6½ Lks.
6" cedar - S62°W - 33½ Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found sq. scribed cedar post, with the cedar, Cons. Dept. N.B.T. in place, living and in good condition. The black spruce had broken off and the stub is now rotted off. Set. D.N.R. monument in place of sq. scribed post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument

5" cedar - N64°W - 17.2'
5" cedar - South - 26.3'
4" cedar - N84°E - 25.15'
6" cedar (old N.B.T.) - S62°W - 22.0'

SIGNED BY David B. Babbitt DATE 9-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: