

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

|   |                           |                           |
|---|---------------------------|---------------------------|
| <u>Menominee</u><br><small>(County)</small> | Located In:               | Corner Code <del>##</del> |
| 1. Public Land Survey                       | T <u>37N</u> R <u>28W</u> | <u>H-3.</u>               |
|   | T _____ R _____           | _____                     |
|   | T _____ R _____           | _____                     |
|   | T _____ R _____           | _____                     |
| 2. Property Controlling<br>in Section       | S _____ T _____ R _____   | _____                     |
|   | S _____ T _____ R _____   | _____                     |
| 3. Miscellaneous<br>Property in Sec.        | S _____ T _____ R _____   | _____                     |
|   | S _____ T _____ R _____   | _____                     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, David B. Babbitt, in a field survey on March 14, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-3. North 1/4 corner of Section 10. Wood post. Tamarac 10, S63E, 45 Lks.  
 W.Pine 16, S70W, 37 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tamarack snag on east side of stream showing both upper and lower faces with scribe marks visible. 1/4 corner position falls in west edge of deep stream. No way of setting a monument that would stay in place in the stream so I set two witness monuments on the north section line of Section 10. One 300.00' east and one 300.00' west of the 1/4 corner position and witnessed both as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument  
 Set on the N. sec. line, Section 10.  
 300.00' west of the 1/4 cor. position  
 11" balsam, N05E-19.7'  
 12" balsam, N66E, 6.3'  
 10" spruce, S09W, 34.2'  
 10" spruce, S26W, 31.0'

DNR Monument  
 Set on the N. sec. line, Section 10.  
 300.00' east of the 1/4 cor. position.  
 8" cedar, S12W, 11.5'  
 5" spruce, N85W, 7.2'  
 5" cedar, N14W, 15.9'  
 6" cedar, N78E, 21.2'

Signed by David B. Babbitt Date 8-1-88  
 Surveyor's Michigan License No. 21558