

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located In:

Corner Code *#*

- | | | |
|---------------------------------------|-------------------------------------|-------------|
| 1. Public Land Survey | T <u>37N</u> R <u>28W</u> | <u>G-6.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S <u>16</u> T <u>37</u> R <u>28</u> | <u>7.</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David B. Babbitt, in a field survey on 3/9/, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-6. E $\frac{1}{4}$ corner of Section 16. Wisconsin Public Service Corp. Drawing #C-7899, dated 3-12-63 shows 4" scribed cedar post set MPOL between the NE and NW section corners of Section 16.
7. N 1/16 E section line, Section 16. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-6. Found scribed post leaning against a tree about 85' southeasterly of MPOL position. Set DNR monument at MPOL between the NE and SE section corners of Section 16 as shown on Wisconsin Public Service Corp. drawing.
7. Set MPOL between the east 1/4 corner and the NE section corner of Section 16.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|------------------------|-----------------------|
| G-6. DNR Monument. | 7. DNR Monument. |
| 9" w.pine N43E, 24.5' | 7" spruce N41W, 54.1' |
| 11" w.pine N83E, 52.0' | 6" oak N85W, 51.7' |
| 7" w.pine S16E, 31.7' | 9" spruce S23W, 36.1' |
| 7" w.pine S28W, 5.35' | 4" spruce N50E, 19.6' |

Signed by David B. Babbitt Date 9-29-88

Surveyor's Michigan License No. 21558