

0726

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>9</u> T <u>37N</u> R <u>28W</u>	<u>16, 15, 7, 14.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 12/23, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 16. East 1/16 corner on the south section line of Section 9. No previous record.
- 15. West 1/16 corner on the south section line of Section 9. No previous record.
- 7. N 1/16 corner on the east section line of Section 9. No previous record.
- 14. S 1/16 corner between Sections 9 and 10. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 16. Set MPOL between the S 1/4 corner and the SE section corner of Section 9.
- 15. Set by single proportion to the GLO record between the S1/4 corner of Section 9 and the meander cor. common to Sections 9 & 16 on the left bank of the Menominee River.
- 7. Set MPOL between the NE section corner and the East 1/4 corner of Section 9.
- 14. Set MPOL between the SE section corner and the East 1/4 corner of Section 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|---|--|---|---|
| 16. DNR Monument.
11" w.pine N38E, 88.8' | 15. DNR Monument.
10" oak S30E, 50.7' | 7. DNR Monument.
7" cedar S65E, 13.45' | 14. DNR Monument
5" cedar S15E, 7.1' |
| 3" maple, S79E, 17.3' | 9" oak S12W, 29.9' | 7" cedar S57W, 8.2' | 8" cedar N40W, 31.5' |
| 4" oak, North, 25.0' | 4" maple N83W, 24.0' | 7" b.spruce, N72W, 7.45' | 5" cedar N60E, 17.4' |
| 9" w.pine, N19W, 65.8' | Balsam N16E, 19.9' | 7" cedar N03W, 17.2' | 12" cedar S65W, 19.2' |

Signed by David B. Babbitt

Date 9-29-88

Surveyor's Michigan License No. 21558