

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>37N</u> R <u>28W</u>	<u>D-3, C-2-MC</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 7/21/, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-3. South 1/4 corner of Section 5. Wood post. August 6, 1849. W.pine 8, N54E, 11 Lks.
 Hemlock 8, S51E, 14 Lks.

C-2-MC. Meander corner common to Section 5&6. Wood post. 1849. Y.pine 16, N65E, .30
 Hemlock 6, N13W, .25

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3. Set by single proportion ~~between~~ to the GLO record between the NE section corner of Section 8 and the probable original position of the meander corner comm. to Sections 5 & 8 on the left bank of the Menominee River. See description of corner C-3-MC.

C-2-MC. Set monument 1.25 chains northwesterly along the Menominee River bank from the mouth of a small stream as recorded in the meander notes of the original gov't. survey. No sign of OBT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3. DNR Monument.	C-2-MC. DNR Monument.
12" w.birch, N15E, 36.2'	6" oak, S11E, 3.5'
5" aspen, S80E, 11.1'	16" oak, N62W, 26.45'
14" r.maple, S24W, 16.7'	6" r.pine, N22E, 78.6'
10" w.birch, N74W, 36.5'	3" w.pine, S84E, 41.9'

Signed by David B. Babbitt Date 9-29-88

Surveyor's Michigan License No. 21558