

01 24.

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>37N</u> R <u>28W</u>	<u>I-3, G-2.</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 5/23/88, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- I-3. SE section corner of Section 3. Wood post. July 31, 1849. B. Ash 8, N68E, 12 lks.  
 Cedar 9, N16W, 36 lks.
- G-2. West 1/4 corner of Section 3. Wood post. 8-3-1849. Cedar 6, N32W, - .23.  
 DO 6, S10W, .09

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-3. Set 50 links south of a small stream and 90 links east of the same stream as recorded in the notes of the original Gov't. survey. This falls in the  $\frac{1}{2}$  of County Road 577 which local residents consider to be on the N-S section line at that point.
- G-2. Found old cedar post point @ south end of very old farm fence. Measurements north 2½ chains and south 2.00 chains agree with the record of the original gov't survey for enter swamp and leave swamp. No sign of OBT's. Set DNR monument @ post point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                        |                       |
|------------------------|-----------------------|
| I-3. DNR Monument      | G-2. DNR Monument     |
| 12" cedar, due W 67.0  | 6" cedar, S38W, 22.1' |
| 20" w.pine, N54E, 68.8 | 8" cedar, N81W, 8.2'  |
| 8" spruce, N58E, 53.5  | 6" cedar, N61E, 33.7' |
| 10" spruce, S70E, 40.8 | 7" cedar, S50E, 21.8' |

Signed by David B. Babbitt Date 9-29-88  
 Surveyor's Michigan License No. 21558