

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------------|
| 1. Public Land Survey | T | <u>37N</u> | R | <u>28W</u> | <u>H-5, I-5.</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 12/22/87, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5. South 1/4 cor. of Section 10. Wood post, 1849. Birch 3" - S45W, 8 Lks.
 Aspen 4" - S64E, 24 Lks.

I-5. SE section corner of Section 10. Wood post, 1849. Spruce 10, N80W, 21 Lks.
 DO 10, N31E, 15 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5. Set MPOL between the SE and SW section corners of Section 10.

I-5. Set according to GLO record to "left bank of stream" 6.00 chs. north and "intersect stream" 1.70 chs. west. GLO call for leave cedar swamp and ascend about 12 ft. at 3.00 chs. east also fits.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5. DNR Monument.	5" oak, N4E, 23.7'	I-5. DNR Monument.	5" cedar, S49W, 32.1'
	7" oak, N49E, 50.5'		5" cedar, S8E, 7.8'
	6" maple, S66E, 35.0'		6" cedar, N33E, 13.8'
	6" maple, S64W, 35.1'		6" cedar, N51W, 32.9'

Signed by David B. Babbitt Date 9-29-88
 Surveyor's Michigan License No. 21558