

OK
2/2

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee

(County)

Located In:

Corner Code #/

- 1. Public Land Survey T 37N R 28W E-3.
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 6/22, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-3. NE section corner of Section 8. Wood post. Hemlock 10" - S56E, .24
DO 10" - N26W, .08

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3. I set this corner from the nearest feature calls (foot of hill 1 chain east and summit of hill 3 chains south) and with knowledge of measurements to meander corner west - 1/4 cor. south 1/2 mile - 1/4 cor. east 1-1/2 miles and the occupied position for the township line north. This position is near record south to the 1/4 cor. common to Sections 8 & 9. It also fits calls for enter and leave tam. swamp. 20.00 chains and 22.00 chains south, and it fits a call for enter cedar swamp 24.00 chains north. There is, however, a shortage of about 250' between this corner position and the occupied township line north. From evaluating all of the feature calls along the line between Sections 4 & 5, it appears that there was a chainage error in the vicinity of the 1/4 cor. The original survey of this twp. was done by James Mullet and wherever I have worked in his surveys, I have found his measurements and bearings to be erratic. William Burt's examination of the line between Sections 28 & 29 of this twp. finds the line to be 1.50 chains longer than James Mullet's record, which is proof that Mr. Mullet's measurements were not accurate. A proportionate position for this corner would not fit the feature calls at all. I, therefore, believe this method restores the corner closer to its

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3. DNR Monument.
6" spruce S8E, 4.6'
5" spruce N80E, 37.8'
5" spruce S69W, 28.9'
6" spruce N25W, 93.7'
E OF NW-SE trail road - West - 19'

original position than any other method I could use.

Signed by David B. Babbitt

Date 12-3-87

Surveyor's Michigan License No. 21558