

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>14</u> T <u>37N</u> R <u>28W</u>	<u>03</u>
	S <u>14</u> T <u>37N</u> R <u>28W</u>	<u>10</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

2/26/2014

, Jeremy J. Pipp, in a field survey on 2/26/2014 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(03) North One-Sixteenth corner common to Sections 14 and 15. Not set in original survey, no evidence of subsequent establishment.

(10) South One-Sixteenth corner common to Sections 14 and 15. Not set in original survey, no evidence of subsequent establishment.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(03) Corner position established mid-point and on-line between the West One-Quarter corner and the Northwest corner of Section 14.

(10) Corner position established mid-point and on-line between the West One-Quarter corner and the Southwest corner of Section 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(03) DNR monument
 10" Cedar N21W 16.03' (1/16S,BT)
 10" Spruce N76E 17.95' (1/16S,BT)
 9" Spruce S16W 11.05' (1/16S,BT)
 5" Maple S79W 19.53' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

(10) DNR monument
 15" W. Pine N40E 61.60' (1/16S,BT)
 4" Spruce S31E 5.12' (1/16S,BT)
 5" Spruce S67W 39.62' (1/16S,BT)
 17" W. Pine N62W 42.55' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by Jeremy J. Pipp
 Surveyor's Michigan License No. 50447



Date July 9, 2014

For the Michigan Department of Natural Resources, Forest Management Division

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													