

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Menominee

(County)

Located In:

Corner Code #

- |                                    |             |                           |          |
|------------------------------------|-------------|---------------------------|----------|
| 1. Public Land Survey              | T           | R                         | _____    |
|                                    | T           | R                         | _____    |
|                                    | T           | R                         | _____    |
|                                    | T           | R                         | _____    |
| 2. Property Controlling in Section | S <u>23</u> | T <u>37N</u> R <u>28W</u> | <u>9</u> |
|                                    | S           | T                         | R        |
| 3. Miscellaneous Property in Sec.  | S           | T                         | R        |
|                                    | S           | T                         | R        |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Dec 08 1999

I, Paul R. Bressette, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (9) East One-sixteenth corner of Section 23. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (9) Corner position established mid-point and on-line between the east quarter and center quarter corners of Section 23.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (9) DNR monument  
 12" Maple N46E 55.6' (1/16S, BT)  
 08" Maple S60E 61.15' (1/16S, BT)  
 09" Maple S51W 8.55' (1/16S, BT)  
 08" Maple N71W 45.2' (1/16S, BT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette  
 Surveyor's Michigan License No. 37270

Date \_\_\_\_\_

For the Michigan Department of Natural Resources - Forest Management Division