

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/26 1999
Mc Davis RLS
Chairman
BK. 6 Pg 48

For corners in
MENOMINEE
(County)

Located In:	Corner Code #
T 37N R 26W	B-09
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD
28 DEC 1998 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	⊙												
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Lenca, in a field survey on June, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Y. Birch, 24" - N40°E - 18 lks.; Elm, 30" - S55°W - 20 lks. All original evidence for this corner has been destroyed by farming activities.
- 1980: L.C.R.C. No. 235 by Ewart Muller, RLS No. 15408, states Fd narrow gage rail on end in rock and stone fence line. Position agrees with field note distances to streams. B.T.'s: Cherry, 8" - N89°E - 23.95'; Elm, 9" - N05°E - 5.75'; Double Black Ash, 5" - S66°W - 17.20'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a narrow gage rail and 3 B.T.'s as described in L.C.R.C. No. 235. This corner fits well with Section Corners 1/2 mile East and 1/2 mile West, has been accepted as the corner position by local surveyors for many years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" dia. x 4' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner.

12" dia. Elm	N04°E	6.15 feet	Scr. NBT
12" dia. Maple	N80°E	34.52 feet	Scr. NBT
14" dia. Tamarack	S40°W	52.67 feet	Scr. NBT
5" dia. Elm	S87°W	29.36 feet	Scr. NBT
Metal Survey Sign Post	N25°E	1.45 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date July 9, 1999

