

SURVEY &
RECORD DOCUMENTATION

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/23, 1999
Mc Davis RLS
Chairman

BK 6 Pg. 49

RECEIVED FOR RECORD
28 DEC 1999 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

For corners in
MENOMINEE
(County)

Located in: Corner Code #

1. Public Land Survey T 37N R 26W B-11
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	31	32	33	34	35	36							
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Cedar, 12" - N58°E - 40 lks.; Y. Birch, 10" - S72°E - 29 lks. All original evidence for this corner has been destroyed by County Road improvements.
- 1988: L.C.R.C. No. 816 by William Lenca, RLS No. 26461, states set 5/8" x 24" Iron Rod/Ident. cap on line and proportionately between the SW Corner and the SE Corner of said Section 30. B.T.'s: 20" Maple - N73°W - 100.15'; 8" Maple - N40°W - 75.44'; 10" Maple - N11°W - 73.86'; c/l Co. Rd. - South - 8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered our 5/8" x 24" iron rod and 3 B.T.'s from our 1988 survey set on line and proportionately between the SW Corner and the SE Corner of Section 30, T37N-R26W, and accepted this location as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S08°W	35.46 feet	
6" dia. White Ash	S68°W	57.38 feet	Scr. NBT
8" dia. Ironwood	N66°W	112.06 feet	Scr. NBT
5" dia. Cedar	N14°E	85.84 feet	Scr. NBT
Metal Survey Sign Post	S08°W	36.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured Total Station. Distances to trees are to nail in side of tree.



Signed by William Lenca 26461
Surveyor's Michigan License No. _____

Date July 9, 1999