

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)

Located In: 37N 26W Corner Code C-2

1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

RECEIVED FOR RECORD
 95 DEC 27 PM 3:31
 PAGE 303 BK 4
 BARBARA M. PERRO
 REGISTER OF DEEDS
 MENOMINEE, MICHIGAN
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

William Lenca Nov. 14, 1995
 I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1852: Original Survey by Francis Coleman - B.T.'s - Ironwood, 6" - N34°E - 15 lks; Hemlock, 8" - S29°W - 23 lks. All original evidence has been destroyed by county road improvements.
 1985: Plat of Survey by William Lenca, RLS No. 26461, shows a tie to this corner. The corner is shown as being in the centerline of an East-West County Road and in line with a fence line South. My notes on this survey indicate that we set a 1/2" x 18" iron rod and took the following witnesses: Power Pole - North - 16.44' (found); SW Corner of Garage - N41°W - 66.03' (found); 30" Maple - S75°E - 78.24' (gone); 30" dia. Box Elder - S01°E - 77.13' (dead).

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 In a 1995 Survey in Section 5, T37N-R26W, we found a 1/2" x 18" iron rod in the centerline of and East - West County Road in line with ancient fence lines North and South and the ties as noted in part "A". This corner position has been used by local surveyors for at least 10 years, and is accepted as the best available evidence of the position of the original corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:
- | | | | |
|---|-------|------------|---------|
| P.K. Nail in Power Pole | North | 16.50 feet | |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | South | 36.97 feet | |
| 4" dia. Cedar | S63°W | 52.96 feet | Scr NBT |
| Metal Survey Sign Post | South | 38.0 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 17, 1995
 Surveyor's Michigan License No. 26461